THE INFORMATION DEPICTED ON THIS MAP REPRESENTS THE RESULTS OF SURVEYS MADE ON THE DATE INDICATED AND CAN ONLY BE CONSIDERED AS INDICATING THE GENERAL CONDITIONS EXISTING AT THAT TIME BECAUSE THESE CONDITIONS ARE SUBJECT TO RAPID CHANGE DUE TO SHOALING EVENTS. A PRUDENT MARINER SHOULD NOT RELY EXCLUSIVELY ON THE INFORMATION PROVIDED HERE.

NAVIGATION AIDS LOCATED BY SURVEY VESSEL, ACCURACY +/- 3 METERS.

	EASTING	NORTHING	LATITUDE	LONGITUDE
POINT 1	3001725	777912	35.84054	75.61952
POINT 2	3001402	777284	35.84159	75.62057
POINT 3	3001431	778604	35.84247	75.62043
POINT 4	3000660	779391	35.84470	75.62294
DOLPHIN CLUSTER	3001506	778448	35.84203	75.62023
DOLPHIN CLUSTER	3001505	778380	35.84185	75.62024

NOTES:

SOUNDINGS ARE EXPRESSED IN FEET AND TENTHS AND REFER TO LOCAL M.L.W..
PROJECT SURVEYED WITH DISTRICT SURVEY VESSEL "BEAUFORT", USING D.G.P.S. HORIZONTAL POSITIONING EQUIPMENT AND 200KHZ SOUNDING EQUIPMENT.

TIDE GAGE LOCATED AT: LT #11 (RANGE 14E)

HORIZONTAL DATUM NAD 1983.

THIS PROJECT WAS DESIGNED BY THE WILMINGTON DISTRICT OF THE U.S. ARMY CORPS OF ENGINEERS. THE INITIALS OR SIGNATURES AND REGISTRATION DESIGNATIONS OF INDIVIDUALS APPEAR ON THESE PROJECT DOCUMENTS WITHIN THE SCOPE OF THEIR EMPLOYMENT AS REQUIRED BY ER 1110-1-8152.

1:600

100 50 0 100 200

SCALE IN FEET

CONDITION SURVEY

SYMBOL	DESCRIPTIONS	DATE	APPROVED
	REVISIONS		

U.S. ARMY ENGINEER DISTRICT
CORPS OF ENGINEERS
WILMINGTON, NORTH CAROLINA

US ARMY CORPS OF ENGINEERS

WANCHESE INNER HARBOR

SURVEYED BY: RWA	SCALE: 1:600	PLATE NUMBER:	SURVEYED: 25 JUNE 2003
DRAWN BY AGF	DATE: 7 JULY 2003		
CHECKED BY			
SUBMITTED BY			
APPROVED BY	MAP FILE NO. MB 105-03-31		SHEET OF
CHIEF, NAVIGATION BRANCH			

.../2003/WANCHESE/wch0625.dgn 08/21/2003 01:54:57 PM